

Addendum #3

**Alterations 2022
Piqua High School
Piqua City Schools**

February 10, 2022

Piqua City School District
215 Looney Road
Piqua, Ohio 45356

This Addendum modifies and shall become a part of the original Contract Documents and is hereby made part of the Bidding Documents for the referenced project.

All bidders shall indicate in their bid/proposal that this Addendum has been received and considered in their bid proposal.

The Addendum items are intended to supplement, clarify or correct parts of the bid proposal package. Items in the addendum shall take precedence over items corrected and shall be of equal value with items supplemented or clarified. Any questions in reference to this addendum must be directed, in writing, to:

Jonathan Schaaf
RDA Group Architects
7945 Washington Woods Drive
Dayton, Ohio 45459
937.610.3440
jrs@rda-group.com

Addendum Items:

1. Drawing Sheet A1.15: Key Note #4: ADD the following the key note: Remove / tooth CMU block, soaps, as required to install new electrical boxes, conduit, devices, etc. within the existing CMU wall. Install new CMU block / soaps as req'd to repair wall and provided a uniform finished appearance. Refer to detail B/ A.1.15.
2. Drawing Sheet H2.06, REPLACE previous sheet with the version attached to this addendum.
 - 2.1. Replace lab hood exhaust fan
3. Drawing Sheet H3.01, REPLACE previous sheet with the version attached to this addendum.
 - 3.1. Update fan schedule
4. Drawing Sheet T1.10: CLARIFICATION of scope:
 - 4.1. The data drawings indicated the data intent for the school. The electrical contractor under this contract is responsible for the conveyance as described in general note U.
 - 4.2. The electrical contractor is responsible for the intercom system function as described in the E-series sheets. This includes removal and reinstallation of the existing equipment into new locations, connections, wiring, connectivity, etc.

End of Addendum #3.