SITE DEVELOPMENT PLANS FOR:

PIQUA HIGH SCHOOL TENNIS & COMPREHENSIVE STORM WATER PLAN

1 INDIAN TRAIL CITY OF PIQUA, MIAMI COUNTY, OHIO

DEVELOPMENT / DESIGN TEAM

CIVIL ENGINEER / CONSULTANT
Burkhardt Engineering
Contact: Jonathan Burkhardt
Phone: 937.388.0060
Email: jdburkhardt@burkhardtinc.com

ARCHITECT

RDA Group Architects
Contact: Jonathan Schaaf
Phone: 937.610.3440
Email: jrs@rda-group.com

PROJECT SUMMARY

Project will include the demolition and removal of utilities, vegetation, pavement, etc. as necessary to construct a new set of tennis courts, buildings, bleachers, a sidewalk, utility extensions, and other associated site improvements. Also included in the scope of work is the expansion of the existing stormwater facility, as well as a new pond outlet structure and improvement to the existing swale that the pond discharges to.


PROPERTY INFORMATION

Address: 1 Indian Trail, Piqua, Ohio 45356
Legal Description: PT IL 7857
Area: 8.339 acres (Tennis Court parcel)
Zoning: CV - Civic District

Flood Zone Designation: FIRM # 39109C0062E, effective date: August 2, 2011.

Zone "X": Areas determined to be outside the 0.2% annual chance floodplain.

Note: Architectural, Structural, Mechanical, Electrical and Plumbing Plans in separate set.



1" = 400'

	SHEET INDEX
C-0.0	TITLE SHEET
C-0.1	GENERAL NOTES
C-1.0	EXISTING CONDITIONS & DEMOLITION PLAN - POND
C-1.1	EXISTING CONDITIONS & DEMOLITION PLAN - SWALE
C-1.2	EXISTING CONDITIONS & DEMOLITION PLAN - TENNIS COURTS
C-2.0	SITE PLAN - POND
C-2.1	SITE PLAN - SWALE
C-2.2	SITE PLAN - TENNIS COURTS
C-3.0	GRADING PLAN - POND
C-3.1	GRADING PLAN - SWALE
C-3.1A	ALTERNATE SWALE
C-3.2	GRADING PLAN - TENNIS COURTS
C-4.0	UTILITY PLAN - POND
C-4.1	UTILITY PLAN - SWALE
C-4.2	UTILITY PLAN - TENNIS COURTS
C-4.3	STORM SEWER PROFILES
C-4.4	STORM SEWER PROFILES
C-4.5	SANITARY SEWER PROFILES
C-5.0	SITE & STORM NOTES & DETAILS
C-5.1	STORM DETAILS
C-5.2	WATER MAIN NOTES & DETAILS
C-5.3	SANITARY NOTES & DETAILS
C-6.0	SWPPP - POND
C-6.1	SWPPP - SWALE
C-6.2	SWPPP - TENNIS COURTS
C-6.3	EROSION CONTROL NOTES AND DETAILS
C-7.0	EXISTING DRAINAGE MAP
C-7.1	PROPOSED DRAINAGE MAP
C-7.2	STORM WATER MANAGEMENT PLAN

* Landscaping is not in the scope of the work. A separate bid package will be completed at a later time.

		Draw		
CIVIL ISSUE LOG				
Description	Date	Scale		
Issued for Bid / Permit / Construction	10.18.2024	Date		
Addendum 4	11.22.2024	1		
		Shee		
		Shee		
		1		
		1		
	ı	7		

Know what's below.
Call before you dig.

The Contractor shall obtain a copy of the Geotechnical Engineering Report prepared by Bowser-Morner, dated January 4, 2024 and shall refer to the report for site preparation, compaction, utility trench backfill, pavement, foundations and slabs, construction and design criteria.

SCHOOL TENN HENSIVE STOR ER PLAN

ENGINEERING | LAND SURVEYIN

Design: MES Proj: 23.191
Draw: MES Dwg:
Check: JDB Tab:

te: 10.18.2024

t: TITLE SHEET

Sheet No.:

C-0.0

GENERAL CONSTRUCTION NOTES

- . Site/Civil Specifications: All plans, construction, materials, workmanship, and methods shall be in accordance with the current "Rules and Regulations" of The City of Piqua and the Ohio Department of Transportation Construction and Material Specifications, current edition. When in conflict, the City of Piqua requirements shall prevail.
- 2. Prior to the start of construction, the Contractor shall be responsible for ensuring that all required permits and approvals have been obtained. No construction or fabrication shall begin until the Contractor has received and reviewed all plans and other documents approved by all the permitting authorities. The Contractor shall post all bonds, pay all fees, and provide proof of insurance as required to obtain permits.
- 3. All sediment and erosion control measures, as shown on Sheets C-6.0, C-6.1& C-6.2, shall be in place prior to the start of any demolition, clearing and grubbing, or construction operations. Erosion control measures shall conform to all Local, State, and Federal regulations and requirements.
- 4. North arrow, existing topography, and property lines based on field survey of the subject property prepared by Burkhardt Engineering in June 2024. An ALTA/NSPS Land Title Survey was not performed, survey may not depict any or all easements impacting the subject property.
- 5. Information on existing utilities has been compiled from available information including utility company and municipal records and field survey and is not guaranteed correct and complete. Utilities are shown to alert the Contractor to their presence and the Contractor is solely responsible for determining actual locations and elevations of all utilities. Prior to demolition or construction, the Contractor shall contact "811", 72 hours before commencement of work and verify all utility locations.
- 6. The Contractor shall provide and maintain traffic control devices for protection of vehicles and pedestrians consisting of drums, barriers, signs, lights, fences and uniformed traffic officers as required by Local and State Authorities.
- 7. The Contractor shall protect all iron pins, monuments and property corners during construction. Any Contractor disturbed pins, monuments, etc. shall be reset by a Professional Land Surveyor (Registered with the State) at the expense of the Contractor.
- 8. Any disturbance incurred to any adjacent properties or public right-of-way during demolition and construction shall be restored to its original condition or better, in accordance with and to the satisfaction of Local and State Authorities.
- 9. The Contractor shall abide by all OSHA, Federal, State, and Local regulations when operating cranes, booms, hoists, etc. in close proximity to overhead electric lines. If Contractor must operate equipment close to electrical lines, contact the local Utility Provider to make arrangements for proper safeguards.
- 10. All material schedules shown on the plans are for general information only. The Contractor shall prepare their material schedules based upon their plan review. All schedules shall be verified in the field by the Contractor prior to ordering materials or performing work.
- the field by the Contractor prior to ordering materials or performing work.

 11. The Contractor shall review all plans prior to construction and immediately report any conflicts
- 12. All work within public rights-of-way shall be in accordance with the The City of Piqua rules, specifications, and regulations.

GENERAL DEMOLITION NOTES

and/or discrepancies to the engineer-of-record.

- 1. Within the subject property, the intent is to have a clean, clear site, free of all existing items noted to be removed in order to allow for the construction of the new project.
- 2. All items noted to be removed shall be done as part of the contract for general construction.
- Remove and dispose of any materials requiring removal from the work area in an approved off-site landfill.
- 4. The Contractor shall secure all permits for demolition and disposal of demolition material to be removed from the site. The Contractor shall post all bonds and pay all permit fees as required.
- . The Contractor shall cut and plug, or arrange for the appropriate utility company to cut and plug service piping at the property line or at the main (as required). All services may not be shown on this plan.
- 6. For all items noted to be removed, remove not only above ground elements, but all underground elements as well, including, but not necessarily limited to: foundations, slabs, gravel fills, tree roots, pipes, wires, unsuitable materials, etc.
- 7. The Contractor shall sawcut existing pavement to provide a clean edge between existing pavement to remain and existing pavement to be removed.
- 3. Limits of removal and sawcut lines shown on demolition plan are approximate only. Actual quantities may vary due to construction activities. Contractor is responsible for all demolition, removal and restoration work necessary to allow for the construction of the new project.
- 9. Backfill excavations resulting from demolition work to meet the requirements for fill outlined in the Geotechnical / Soils Report.

GENERAL SITE NOTES

- 1. Building dimensions shown on the Civil Engineering Plans are for reference purposes only. The Contractor shall use the Architectural and Structural Plans for exact building dimensions.
- 2. All site and radii dimensions are referenced to the face of curbs or edge of paving unless otherwise noted.
- 3. All dimensions to the building are referenced to the outside face of the foundation wall.
- 4. All sidewalks, curb and gutter, street paving, curb cuts, driveway approaches, handicap ramps, etc. constructed outside the property line in the right-of-way shall conform to all Local and/or State specifications and requirements.
- All proposed handicap ramps, parking areas, and accessible routes shall strictly comply with current Local, State, and Federal regulations, including but not necessarily limited to the ADA Accessibility Guidelines (ADAAG).
- 6. All ADA accessible routes shall have detectable warnings installed as required by the ADAAG. Detectable warnings shall consist of raised truncated domes which contrast visually with the adjoining surfaces, either light-on-dark, or dark-on-light.
- 7. Contractor shall sawcut existing pavement to provide a clean, straight joint where new pavement meets existing pavement and ensure positive drainage.
- 8. All concrete pavement shall have joints in accordance with ACI 330R-08, Section 3.7 and Appendix C. Contraction joints shall be 1/4 of the slab thickness. Isolation joints shall be placed between pavement and foundations, inlets, and other fixed structures. Contraction joints shall be tool finished and spaced as follows:

Curbing: 10'-0" (max) spacing.
Sidewalks: 5'-0" (max) spacing.
Vehicular Traffic Areas: 24 x Concrete Pavement

GENERAL GRADING, EARTHWORK & DRAINAGE NOTES

Thickness (feet), 15'-0" (max) spacing.

- 1. All spot elevations indicated in pavement areas are at bottom face of curb and/or finished pavement grade unless noted otherwise. All spot elevations indicated in grass or landscape areas are finished grade unless noted otherwise.
- 2. The Contractor shall be responsible for the removal and disposal of all vegetation and organic materials from the site that results from clearing & grubbing activities.
- 3. The Contractor shall be responsible for stripping and removal of all excess topsoil from the site. All topsoil that cannot be used on site shall be removed from the site at the Contractor's expense. The Contractor may dispose of excess topsoil by burying topsoil in landscape areas only at the direction of the Owner or the Owner's Representative.
- 4. The Contractor will be responsible for all safety requirements and for the protection of all existing and proposed utilities or structures during earthwork procedures.
- 5. The Contractor shall be responsible for the import of structural fill materials if suitable material is not available on site. The location and testing of suitable material shall be the Contractor's responsibility. The Contractor shall be responsible for the export and disposal of all excess or unsuitable materials.
- 6. The Contractor shall provide construction dewatering as necessary to complete construction as outlined in plans.
- 7. The Contractor shall exercise extreme care in establishing all grades and slopes in pavement areas, ramps and sidewalks in the vicinity of handicap parking and access areas and shall comply with Federal, State, and Local Codes.
- 8. In areas where sheet drainage flows from grass or landscape areas onto paved areas, the finished grade in grass or landscape areas shall be 1/2 inch above the top of curb or above the pavement in areas without curb. In areas where sheet drainage flows from pavement to grass or landscaped areas, the finished grade in grass or landscape areas shall be 1/2 inch below the pavement.
- 9. The Contractor shall provide positive drainage in all areas and away from all buildings.
- 10. All pavement shall be laid on a straight, even, and uniform grade with a minimum of 1:100 (1.0%) slope toward the collection points unless otherwise specified on plans. Cut or fill slopes in unpaved areas shall not exceed 3:1 (33.3%) maximum grade unless otherwise noted on plans.
- 11. ADA accessible areas shall not exceed the following slopes:

Ramps - 1:12 (8.3%) max.

Routes - 1:20 (5.0%) max.

Parking - 1:50 (2.0%) max.

Cross Slopes - 1:50 (2.0%) max.

- 12. The Contractor shall adjust tops/lids/grates of all cleanouts, manholes, inlets, valves, etc. to match final grade.
- 13. Following grading of subsoil to subgrade elevations, the Contractor shall provide 4" of topsoil (minimum) in all disturbed areas which are not to be paved. Final grades should be smoothly finished to surrounding areas and ensure positive drainage. Stockpiled topsoil shall be screened prior to respreading and should be free of subsoil, debris, and stones.
- 14. The Contractor shall apply hydroseed and establish permanent lawn vegetation (grass) in all areas disturbed by construction (including rights-of-way and adjacent properties), unless otherwise specified on landscape plans. Hydroseed application rate, mulch, fertilization, and watering shall be appropriate for the local climate and soil conditions, to ensure a healthy stand of lawn
- 15. The Contractor shall be responsible for determining exact quantities of cut and/or fill for estimating and construction and should alert the Engineer of any excessive cut and/or fill, especially if additional cut and/or fill will be required due to poor existing soil conditions discovered during earthwork operations.
- 16. Refer to the Architectural and Structural Plans for information regarding any perimeter foundation drains & downspout locations.
- 17. The Contractor shall obtain a copy of the Geotechnical / Soils Report and become thoroughly familiar with site and subgrade information and fully implement recommendations given therein.
- 18. The Contractor shall provide geotextile weed mat under all landscape mulch/stone and rip-rap.

 19. If field tiles are encountered, notify Engineer, field tiles will likely need to be replaced and
- 19. If field tiles are encountered, notify Engineer, field tiles will likely need to be replaced and connected to storm sewer system.

GENERAL UTILITY NOTES:

- 1. All utilities shown are approximate locations only and have been compiled from the latest available mapping. The exact location of all underground utilities shall be verified by the Contractor prior to the start of construction.
- 2. Contractor to coordinate with the local utility companies for all locations and connections. A preconstruction meeting with the various utility companies may be required prior to the start of any construction activity.
- 3. The Contractor shall visit the site and verify the location, elevation, and condition of all existing utilities by various means prior to beginning any excavation. Test pits shall be dug at all locations where existing and proposed utility lines cross, and the horizontal and vertical locations of the utilities shall be determined. The Contractor shall contact the Engineer in the event of any unforeseen conflicts between existing and proposed utilities so that an appropriate modification may be made.
- 4. The Contractor shall ensure that all utility companies and local standards for materials and construction methods are met. The Contractor shall perform proper coordination with the respective utility company. The Contractor shall coordinate work to be performed by the various utility companies and shall pay all fees for connections, disconnection, relocations, inspections, and demolition.
- 5. This plan details pipes up to 5' from the building face. Refer to the building drawings for building connections. Supply and install pipe adapters as necessary.
- 6. All valve boxes and curb boxes shall be adjusted to the final grades and located in grassed areas unless indicated otherwise on the plans.
- 7. The Contractor shall provide traffic bearing concrete collars and lids for all cleanouts, manholes, inlets, valves, etc. which are located in paved areas.
- All existing pavement within the rights-of-way where utility piping is to be installed shall be saw cut and replaced or directionally bored in accordance with Local and/or State requirements.
 Existing pavement shall be repaired as necessary.
- 9. All utility lines and trenches shall be installed, bedded and backfilled according to manufacturer's specifications and to the satisfaction of Local and State Authorities.
- 10. Sanitary sewer laterals shall maintain (10' min. horizontal, 1.5' min. vertical) separation distance from water lines unless otherwise shown, or additional protection measures will be required. Where water line crosses above sanitary lateral by less than 2' vertical, a concrete encasement shall be installed, Contractor shall center one joint of pipe at crossing.
- 11. Roof drains, foundation drains, and other clean water connections to the sanitary sewer system are prohibited.
- 12. The Contractor shall prepare and submit shop drawings of all site utility structures and materials to engineer-of-record for review, prior to ordering materials or construction.

SANITARY SEWER NOTES:

Contractor to provide 8" (max.) sanitary sewer service line, as depicted, to service proposed tennis court restrooms and future improvements. Install tap, manholes, cleanouts and other appurtenances as required by the local utility provider. Coordinate building connection with plumbing plans.

All sanitary sewer pipe shall be P.V.C. SDR 35, ASTM D-3034 with joints conforming to ASTM 3212. All pipe shall be installed in accordance with the manufacturer's recommended procedures and shall maintain a minimum slope of 0.40% for 8" and 2% for 4".

Sanitary sewer clean-outs shall be installed at all sewer pipe bends, angles, and junctions, unless a manhole is indicated. All cleanouts in pavement areas shall be installed with traffic bearing lids and concrete collars. Cleanout spacing should not exceed 100'. Per detail / Sheet C-5.3.

Contractor to confirm sanitary inverts shown on this plan (as they exit the building) match what is provided on the Plumbing Plans, notify engineers of any conflicts.

Sanitary sewer service connection, permit and construction to be coordinated with the City of Piqua.

WATER NOTES

Contractor to provide new water services, as depicted, to service proposed tennis court restrooms and future improvements. Install tap, valves, meter, backflow preventer, and other appurtenances as required by the local utility provider. Coordinate building connection with Plumbing Plans.

All water main pipe shall be AWWA C-151 Ductile Iron Pipe, Class 52. Mains shall be installed with a minimum cover of 54" or below frost line, whichever is greater.

Water main connection, permit and construction to be coordinated with The City of Piqua.

STORM SEWER NOTES

All storm sewer shall be reinforced concrete pipe (RCP, ASTM C76 - Class IV, minimum) or high-density polyethylene pipe (ADS N-12 WT, watertight, or equivalent), unless otherwise noted on plans. All pipe shall be installed according to manufacturer's specifications. All storm sewer pipe and joints to be watertight, including the downspout collection system.

Contractor to provide downspout collection system to connect building downspouts / roof drains to storm sewer system. See architectural plans for downspout locations.

Downspout collection pipe (DCP) may be HDPE (ADS N-12 WT, watertight, or equivalent) or Schedule 40 PVC pipe. All downspout collector pipes to be at 1.00% minimum slope. All pipe shall be installed according to Local, State, and manufacturer's specifications. Provide cleanouts at all bends, angles, and junctions. All cleanouts in pavement areas shall be installed with traffic bearing lids and concrete collars, per detail on Sheet C-5.0.

Contractor to provide tennis court underdrain system, according to specifications provided by Geotechnical Engineer and Tennis Court Designer.


Contractor to provide steps, as required by ODOT and OSHA, in all catch basins and manholes. All catch basins installed in sump areas to have finger drains as detailed on Sheet C-5.0.

Storm sewer connection, permit and construction to be coordinated with the City of Piqua.

ELECTRIC NOTES:

Coordinate electric service lines, transformer, meter, and connections with Electrical Plans and local utility provider. Contractor shall verify both location and availability of service prior to the start of construction.

Coordinate site lighting, signage wiring, conduit locations, connections, etc. with electrical plans. Notify Engineers of any potential conflicts.



IQUA HIGH SCHOOL TENNIS COMPREHENSIVE STORM WATER PLAN



Check: JDB Tab:
Scale: AS SHOWN

Design: MES Proj: 23.191


Draw: MES Dwg:


10.18.2024 heet:


GENERAL NOTES

eet No.:









SITE DEVELOPMENT PLANS FOR:
PIQUA HIGH SCHOOL TENN
& COMPREHENSIVE STORI
WATER PLAN

ENGINEERS V SURVEYOR STREET | BURKHARDTING.COM


Design: MES Proj: 23.191
Draw: MES Dwg:
Check: JDB Tab:

Scale: AS SHOWN

Date: 10.18.2024

Sheet:
EXISTING CONDITIONS
& DEMOLITION PLAN SWALE

eet No.:




11/22/2024 11:18:23




Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab: Scale: AS SHOWN

10.18.2024

EXISTING CONDITIONS & DEMOLITION PLAN -TENNIS COURTS







			1871, 1871,	(C)/OII	/ST VA 1	ERE TIII	2/1	(2)			
		1			20				3:23	3 A	•
Date	11/22/2024										
n Description	ADDENDUM 4										
Item	_										
		U,)	5	5						

PIQUA HIGH SCHOOL TENNIS & COMPREHENSIVE STORM WATER PLAN





Design: MES Proj: 23.191
Draw: MES Dwg:
Check: JDB Tab:
Scale: AS SHOWN


Date: 10.18.2024


SITE PLAN - SWALE

neet No.:









JA HIGH SCHOOL TENNOMPREHENSIVE STOR WATER PLAN




Design: MES Proj: 23.191
Draw: MES Dwg:
Check: JDB Tab:
Scale: AS SHOWN


Date: 10.18.2024

1U.18.2U24 eet:

GRADING PLAN -SWALE

C-3.1







Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab:

10.18.2024

ALTERNATE SWALE

(ALTERNATE #7)









Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab: Scale: AS SHOWN

10.18.2024


GRADING PLAN -TENNIS COURTS






UTILITY LEGEND PROP. CLEANOUT PROP. CATCH BASIN PROP. MANHOLE (SAN. OR STM.) PROP. SANITARY SEWER PROP. STORM SEWER PROP. WATER SERVICE

Sanitary sewer, storm sewer, water, gas, electric, and telecom utilities, servicing the football stadium, could not be located or may not be depicted in their exact locations. Contractor shall locate at the start of construction and notify engineers of any conflicts. Existing utility services to the football stadium may need to be relocated or reburied to mitigate conflicts with proposed storm sewer and sanitary sewer.




L TENNIS E STORM VELOPMENT PLANS FOI H SCHOOL EHENSIVE S ATER PLAN 1 INDIAN TRAIL 1, MIAMI COUNTY, OHIO




Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab: Scale: AS SHOWN

UTILITY PLAN -**SWALE**

1 inch = 40 ft.





11/22/2024 11:18:24 /


TENNIS TORM


ANS FO


Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab: Scale: AS SHOWN


10.18.2024


STORM SEWER **PROFILES**











L TENNIS

S STORM HOOL PIQUA HIG & COMPI


11/22/2024 11:18:24 A


Design: MES | Proj: 23.191 Draw: MES Dwg:


Check: JDB Tab: Scale: AS SHOWN

Date: 10.18.2024


STORM SEWER **PROFILES**
















PIQUA HIC & COMPF


Draw: MES Dwg: Check: JDB Tab: Scale: AS SHOWN Date: 10.18.2024


Design: MES | Proj: 23.191


SANITARY SEWER PROFILES















SIDEWALK TO BE CONSTRUCTED USING 3500 PSI CONCRETE. 2. SIDEWALK TO HAVE TOOLED CONTROL JOINTS NOT EXCEEDING 5 FT. SPACING IN ANY DIRECTION.

3. PROVIDE THICKENED EDGE / TURN DOWN WHERE SIDEWALK

MEETS ASPHALT PAVEMENT. 4. PROVIDE EXPANSION JOINT MATERIAL WHERE SIDEWALK ABUTS


> **CONCRETE SIDEWALK DETAIL** NOT TO SCALE



HDPE PIPE MAY BE SUBSTITUTED WITH PVC PIPE. ALL JOINTS ARE TO BE WATERTIGHT. CLEAN OUT TO HAVE TRAFFIC BEARING LID AND

CONCRETE COLLAR IF INSTALLED IN PAVEMENT AREAS.

DOWNSPOUT COLLECTOR **CLEAN-OUT DETAIL** NOT TO SCALE



Know what's below. Call before you dig. *COMPACT AND PROOF ROLL ALL AREAS PRIOR TO BASE COURSE PLACEMENT. APPLY PRIME COAT AND TACK COAT IN ACCORDANCE WITH ODOT

ASPHALT CONCRETE, ITEM 403 OR 404

A - 2.0" ASPHALT SURFACE COURSE

CRUSHED AGGREGATE, ITEM 304

D - COMPACTED SUBGRADE, ITEM 204


C - 4.0" BASE COURSE

SPECIFICATIONS.

RECOMMENDATIONS.


ASPHALT PATH SECTION NOT TO SCALE

*PAVEMENT SECTION PER GEOTECHNICAL



SEE GEOTECHNICAL REPORT PREPARED BY BOWSER-MORNER DATED JANUARY 4, 2024 FOR ADDITIONAL INFORMATION.

CONCRETE **PAVEMENT SECTION** NOT TO SCALE



CATCH BASIN FINGER DRAIN DETAIL NOT TO SCALE

11/22/2024 11:18:24

źŌ


Z


Design: MES Proj: 23.191


Check: JDB Tab: Scale: AS SHOWN 10.18.2024


Draw: MES Dwg:

SITE & STORM **NOTES & DETAILS**














SITE DEVELOPMENT PLANS FOR:

IQUA HIGH SCHOOL TENI

COMPREHENSIVE STOF

WATER PLAN



Oraw: MES Dwg:
Check: JDB Tab:
Cocale: AS SHOWN


Date: 10 19 2024


e: 10.18.2024


Design: MES Proj: 23.191

eet: STORM DETAILS

No.:










800-5

02-08-17 BG







Z SITE SITE IN THE S




Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab: Scale: AS SHOWN


10.18.2024


WATER MAIN NOTES & DETAILS

C-5.2









SPECIFICATIONS

ASTM D-3034

SPECIFICATIONS

ANSI A-21.1


APPROVED: DEC. 2016


PAGE No.


900-13


12-30-16 BG


ELASTOMERIC













11/22/2024 11:18:24




Check: JDB Tab: Scale: AS SHOWN


10.18.2024


SANITARY NOTES &

DETAILS










GENERAL STORMWATER POLLUTION PREVENTION NOTES

- All erosion and sediment control practices must conform to the standards and specifications set forth by the Local, State, and Federal Authorities.
- Construction activities shall be scheduled such that a minimum area of the site is disturbed at a time. Construction operation shall be scheduled and performed so that preventative soil erosion control measures are in place prior to excavation in critical areas and temporary stabilization measures are in place immediately following backfilling operations. Contractor shall reduce effects of storm water by using and/or maintaining grassed swales, infiltration structures, or water
- Special precautions will be taken in the use of construction equipment to prevent situations that
- Cleanup will be done in a manner to ensure that erosion control measures are not disturbed.
- The soil erosion controls are to be inspected once a week and within 24 hours of a 0.50 inch or greater rain event. A written log of these inspections and improvements to controls shall be kept on site. The logs shall include the date of inspection, name of the inspector, weather conditions, actions taken to correct any problems and the date corrective actions were taken.
- Temporary soil stabilization shall occur within 7 days after rough grading if the area will remain idle longer than 14 days. Any disturbed area that is not going to be worked for 365 days or more must be permanently stabilized (seeded and mulched) within 7 days of most recent disturbance.
- Trenches for underground utility lines and pipes shall be temporarily stabilized within 7 days if they are to remain inactive for 14 days. Trench dewatering devices shall discharge in a manner that filters soil-laden water before discharging it to a receiving drainage ditch or pond. If seeding, mulching or other erosion and sediment control measures were previously installed; these protective measures shall be reinstalled. Pipelines with joints that allow a manufactured length of pipe to be placed in the trench with the pipe joint assembled/made in the trench require an open pipeline trench that is only slightly longer than the length of pipe being installed. The total length of excavated trench open at any time should not be greater than the total length of pipeline/utility that can be placed in the trench and backfilled in one working day. No more than 50 linear feet of open trench should exist when pipeline/utility line installation ceases at the end of the work day.
- Soil stockpiles shall be stabilized or protected to prevent soil loss.
- All disturbed areas shall be permanently stabilized within 7 days of final grading. Further, soil erosion control measures shall be maintained until permanent stabilization is complete, at which time temporary measures will be removed. Permanent vegetation is a ground cover dense enough to cover 80% of the soil surface and mature enough to survive winter weather conditions.
- 10. Silt fence to be 2' minimum from property lines in areas where work is near adjacent properties.
- 11. The Contractor shall establish a permanent on-site benchmark prior to clearing, grubbing and/or demolition.
- 12. Haul Routes The Contractor shall be responsible for the cleanup of any mud, dirt, or debris deposited on haul roads as a result of his operations. Soil shall be removed from roads and paved surfaces at the end of each day in such a manner that does not create off-site sedimentation in order to ensure safety and abate off-site soil loss. Collected sediments shall be placed in a stable location on site or taken off-site to a stable location. Contractor shall use State Routes (and shortest distance non-state routes) for project haul route.
- No solid or liquid waste shall be discharged into storm water runoff.
- 14. Disposal of solid, sanitary and toxic waste Solid, sanitary and toxic waste must be disposed of in a proper manner in accordance with local, state and federal regulations. It is prohibited to burn, bury or pour out onto ground or into storm sewer any solvents, paint, stains, gasoline, diesel fuel, used motor oil, hydraulic fluid, antifreeze, cement curing compounds and other such toxic or hazardous waste.
- 15. Wash out of cement trucks should occur in the designated area where the washing can collect and be disposed of properly when it hardens
- 16. If a concrete washout area, and/or a stockpile area are needed, a delineated area for each must be provided and maintained for them. Areas can be located in an alternate location than that shown on the plans if necessary due to construction operations and other field considerations.
- 17. No fuel storage is permitted on-site.
- 18. All storm sewers, infiltration, detention, and retention areas shall be cleared of construction sediment upon completion of construction.
- 19. The General Contractor shall be responsible for submitting a Notice of Intent (NOI) and Notice of Termination (NOT) as required by the Ohio EPA.
- 20. The General Contractor is responsible for ensuring that all soil erosion and sediment control practices comply with the Ohio EPA's General Permit for Construction No. OHC000005 and follow the best practices set forth in the ODNR Rainwater and Land Development Manual.
- 21. Dumpsters shall be provided for the disposal of debris, trash, hazardous and petroleum waste. All containers must be covered and leak proof.
- 22. All construction and demolition debris waste will be disposed of in an OEPA approved C&DD landfill as required by Ohio Revised Code 3714
- 23. Any areas that will be used for mixing or storing fertilizers, lime, asphalt or concrete or used for vehicle fueling shall be designated and these areas should be kept away from any watercourses or storm sewers.
- 24. A Spill Prevention Control and Countermeasures (SPCC) Plan shall be developed if the site has one above ground storage tank of 660 gallons or more, total above ground tank storage of 1330 gallons, or below ground storage of 42,000 gallons of fuel.
- 25. All contaminated soils must be treated and/or disposed in OEPA approved soild waste management facilities or hazardous waste treatment, storage or disposal facilities (TSDFs).
- 26. In the event of a large release of petroleum waste (25 gallons or more) contractor shall contact OEPA at 1-800-282-9378, the local fire department and the local emergency planning committee (LEPC) within 30 minutes of spill.
- 27. Protected storage areas for industrial or construction materials shall be used to minimize exposure of such materials to storm water.
- 28. If the Contractor uses pumps to assist in construction dewatering efforts, the water must be filtered prior to discharging it into the municipal storm sewer system, ensuring that no soil, silt or sediment enters the system.
- 29. Contractor to review and determine the best locations for construction entrance, concrete washout, dumpsters, and other SWPPP elements. All dirt and sediment is to be kept off public
- 30. Contractor shall coordinate all soil erosion control and construction entrance with the City of



SOIL EROSION CONTROL SEQUENCE OF CONSTRUCTION

- 1. Stone tracking pad atop geotextile liner.
- 2. Install silt fence and protection fencing.
- 3. Install sediment basin.
- 4. Initial clearing, grubbing, and demolition.
- 5. Strip and stockpile top soil.
- 6. Rough grade and balance site.
- 7. Install underground utilities (i.e. Sanitary, Storm & Water)
- 8. Place inlet filters on all storm inlets 9. Install franchise utilities (i.e. Gas, Electric, Telephone & Cable TV).
- 10. Final grade site.
- 11. Install pavement, curb, and other hardscape structures/surfaces.
- 12. Stabilize ditches, swales, common areas and slopes. 13. Establish permanent vegetation for all disturbed areas.
- 14. Remove all temporary erosion and sediment control devices.
- 15. Clean out storm sewer system, infiltration, detention, and retention areas upon completion.

SOIL EROSION CONTROL MAINTENANCE

- •Inlet protection devices and barriers shall be repaired or replaced if they show signs of undermining or deterioration.
- All seeded areas shall be checked regularly to see that a good stand is maintained. Areas should be fertilized, watered, and reseeded as necessary.
- Silt fences shall be repaired to their original conditions if damaged. Sediment shall be removed from the silt fences when it reaches one-half the height of the silt fence.
- The construction entrance shall be maintained in a condition which will prevent tracking or flow of mud onto public rights-of-way.
- Sediment from the storm sewers, infiltration, detention, and retention areas shall be removed as necessary to maintain proper functionality.

SOIL EROSION CONTROL PRODUCT NOTES

All stormwater inlets shall be protected with Geotextile Inlet Protection or Inlet Filters (Dandy Products, Flexstorm, or equivalent).

INSPECTION NOTES

- •Inspections shall be made weekly and within 24 hours after a rain event of 0.5 inches within a 24 hour period. Inspection frequency may be reduced to monthly for dormant sites if the entire site is temporarily stabilized or if runoff is unlikely due to weather conditions for extended periods of time. Only qualified inspection personnel shall perform inspections.
- •Inspection checklist shall be completed and signed by the inspector after every inspection. The inspection checklist shall contain the following: date, name/title/qualifications of inspectors, weather for the period since the last inspection (rainfall amounts, duration, etc.), weather and description of any discharges occuring at time of inspection, location of discharges or other pollutants from the site, location of BMP needing maintenance, location of any failed BMPs, location for additional BMPs needed based on inspection, corrective actions required including any changes to the SWP3
- and implementation dates. • The inspection records are to be kept 3 years after termination of construction activity.
- •Non sediment pond BMPs are to be repaired 3 days after inspections and sediment ponds to be repaired or cleaned out within 10 days after inspection.
- •If a BMP is not functioning like it was intended to it shall be replaced within 10 days of inspection.
- For missing BMPs they shall be installed within 10 days of inspection.

SITE OVERVIEW:

NATURE OF CONSTRUCTION ACTIVITY: The proposed improvements will include constructing a new set of tennis courts, buildings, bleachers, a sidewalk, utilities, and other associated site improvements. Runoff from the site will be collected in a new storm sewer system and routed through an improved Wet Extended Detention Basin, providing both Water Quality Volume and Detention Volume controls to reduce post-construction runoff rates in accordance with the Ohio EPA and City of Piqua Regulations. Mass grading will be performed as necessary to construct the project and we anticipate that a significant amount of existing soil will need to be transported off site due to the poor existing soil conditions as well as the grading cuts expected. Soil erosion control measures will be implemented throughout construction to prevent soil, silt, and other debris from entering the public storm sewer system.


TOTAL AREA TO BE DISTURBED: Approximately 13.64 acres will be disturbed.

EXISTING SOILS: Site consists of Brookston Silty Clay Loam, Celina Silt Loam, Crosby Silt Loam, Crosby Silt Loam, and Odell Silt Loam.

EXISTING LAND USE: Land is currently used as a crop field with some lawn space and woods. Land use will change to a tennis court and sidewalk with a pond addition and lawn space. Property is not known to have had hazardous or solid waste.

NAME OF SURFACE WATER: The storm water enters an existing 54" culvert opening near the rear of the Upper Valley Career Center and ultimately drains into Garbry Creek.

WETLANDS: There are no wetlands in the work area.



- 1. INLET PROTECTION SHALL BE CONSTRUCTED EITHER BEFORE UPSLOPE LAND DISTURBANCE BEGINS OR BEFORE THE STORM DRAIN BECOMES OPERATIONAL
- 2. THE EARTH AROUND THE INLET SHALL BE EXCAVATED COMPLETELY TO A DEPTH AT
- 3. THE WOODEN FRAME SHALL BE CONSTRUCTED OF 2-BY-4-IN. CONSTRUCTION-GRADE LUMBER. THE 2-BY-4-IN. POSTS SHALL BE DRIVEN 1 FT. INTO THE GROUND AT FOUR CORNERS OF THE INLET AND THE TOP PORTION OF 2-BY-4-IN. FRAME ASSEMBLED USING THE OVERLAP JOINT SHOWN. THE TOP OF THE FRAME SHALL BE AT LEAST 6 IN. BELOW ADJACENT ROADS IF PONDED WATER WOULD POSE A SAFETY HAZARD TO TRAFFIC.
- 4. WIRE MESH SHALL BE OF SUFFICIENT STRENGTH TO SUPPORT FABRIC WITH WATER FULLY IMPOUNDED AGAINST IT. IT SHALL BE STRETCHED TIGHTLY AROUND THE FRAME
- AND FASTENED SECURELY TO THE FRAME GEOTEXTILE SHALL HAVE AN EQUIVALENT OPENING SIZE OF 20-40 SIEVE AND BE RESISTANT TO SUNLIGHT. IT SHALL BE STRETCHED TIGHTLY AROUND THE FRAME AND FASTENED SECURELY. IT SHALL EXTEND FROM THE TOP OF THE FRAME TO 18 IN. BELOW THE INLET NOTCH ELEVATION. THE GEOTEXTILE SHALL OVERLAP ACROSS ONE SIDE OF THE INLET SO THE ENDS OF THE CLOTH ARE NOT FASTENED TO THE SAME
- 6. BACKFILL SHALL BE PLACED AROUND THE INLET IN COMPACTED 6-IN. LAYERS UNTIL EARTH IS EVEN WITH NOTCH ELEVATION ON ENDS AND TOP ELEVATION ON SIDES.
- 7. A COMPACTED EARTH DIKE OR A CHECK DAM SHALL BE CONSTRUCTED IN THE DITCH LINE BELOW THE INLET IF THE INLET IS NOT IN A DEPRESSION AND IF RUNOFF BYPASSING THE INLET WILL NOT FLOW TO A SETTLING POND. THE TOP OF EARTH DIKES SHALL BE AT LEAST 6 IN. HIGHER THAN THE TOP OF THE FRAME.

INLET PROTECTION DETAIL




DISTURBED AREA CALCULATIONS AND RUNOFF COEFFICIENTS

Total Area Disturbed = 13.64 Acres

Pre-Developed Condition: Percent Impervious = 0.00% (13.64 Acres) Runoff Coefficient = 0.20

Post-Developed Condition: Percent Impervious = 15.0% (2.35 Acres) Runoff Coefficient = 0.33


*Runoff Coefficient Used for Impervious Areas = 0.95 *Runoff Coefficient Used for Lawns = 0.20




1. PLASTIC LINER SHALL BE ANCHORED WITH GRAVEL-FILLED BAGS

2. CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 10' OF THE CONCRETE WASHOUT AREA.

NOT TO SCALE




NOT TO SCALE



SILT FENCE & INLET PROTECTION INSTALLATION DETAIL






ROCK CHECK DAM IS TO BE REMOVED ONCE ALL CONSTRUCTION IS COMPLETE AND PERMANENT VEGETATION HAS BEEN ESTABLISHED.

INTENT OF ROCK CHECK DAM IS TO PREVENT SOIL, DEBRIS, AND OTHER CONSTRUCTION CONTAMINANTS FROM BEING RELEASED INTO THE PUBLIC STORMWATER SYSTEM AND DOWNSTREAM WATERS OF THE STATE.

> TEMPORARY ROCK CHECK DAM NOT TO SCALE






1. STONE SHALL BE 1.5"-2.5" IN DIAMETER 2. GEOTEXTILE FABRIC SHALL BE LAID OVER THE ENTIRE AREA PRIOR TO PLACING

STONE. (US 200 OR EQUIV.)

CONSTRUCTION ENTRANCE DETAIL NOT TO SCALE



źŌ-₹ō




Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab: Scale: AS SHOWN


10.18.2024

EROSION CONTROL NOTES AND DETAILS

C-6.3



EXISTING DRAINAGE MAP










11/22/2024 11:18:24 A



PROPOSED DRAINAGE MAP









Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab: Scale: AS SHOWN

Date: 10.18.2024

PROPOSED
DRAINAGE MAP





TOTAL SITE & DETENTION BASIN PERFORMANCE TABLE

Event (yr)	Total Site Pre Development Peak Discharge (cfs)	Total Site Post Development Peak Discharge (cfs)	Total Site Allowable Peak Discharge (cfs)	Detention Basin Peak Discharge (Outflow) (cfs)	Detention Basin Water Surface Elevation	Basin Volume (cu.ft.)
1	40.85	17.57	40.85	3.16	939.49	414,554
2	61.30	26.35	40.85	3.90	939.99	554,661
5	91.22	39.41	40.85	4.80	940.68	755,047
10	116.19	50.69	116.19	5.47	941.26	925,675
25	153.04	66.49	153.04	6.32	942.09	1,175,605
50	183.50	78.70	183.50	6.96	942.77	1,385,316
100	202.36	92.90	202.36	7.57	943.49	1,608,647

Critical Storm = 5 year storm

BOTTOM OF POND = 932.00

(SEE NOTES BELOW)

2023 HydroCAD used for storm water calculations and detention modeling.

DETENTION BASIN STAGE-STORAGE-DISCHARGE

Elevation (ft)	Contour Area (sq.ft.)	Incremental Storage (cu.f.t)	Total Storage (cu.ft.)	Discharge (cfs)
938.00	271,535	0	0	0.00
939.00	279,348	275,442	275,442	2.67
940.00	287,239	283,293	558,735	4.63
941.00	295,206	291,223	849,958	5.98
942.00	303,251	299,228	1,149,186	7.07
943.00	311,372	307,312	1,456,498	8.02
944.00	319,571	315,471	1,771,969	18.12
944.50	338,599	130,873	1,902,842	27.46

•	Basin WQv Complia	ance Tool			
Project Summary	<u> </u>	-		i	
			_		
Project Name:	Piqua High School Storm Water Expansion				
Subwatershed ID/Label:	PROPOSED TO POND				
Submitted by:	Mark Schott				
Date:	11/20/2024				
Subwatershed Drainage Area, Atotal =	117.81	acres	=	5,131,804	ft2
Subwatershed Impervious Area, Aimp =	63.01	acres	=	2,744,498	ft2
Imperviousness fraction, i =	0.53			53	%
Water Quality Volume, WQv =	204,498	ft3	┇	4.69	ac-ft
Step 1 - Soil Suitability					
Soil Series	Bs, CeB, CrA, CrB &	L AbO &		HSG	С
Juli Jeries	23, 663, 617, 612 6	, our		1130	-
Step 2 - Wet ED Basin Volume Requirements		<u> </u>		1	<u> </u>
Extended Detention Volume, EDv =	204498	ft3			
Minimum Sediment Storage Volume, Vsediment =	40900	ft3			
Minimum Permanent Pool Volume, PPv =	245397	ft3			
, and the second	243337	113			
Step 3 - Basin Stage-Storage Relationship					
				Incremental	Cumulative
	Elevation	Area		Volume	Volume
	ft	ft2		ft3	ft3
Bottom of Permanent Micropool =	932.00	221023			
<u> </u>	933.00	227314		224,161	224,161
	934.00	233621		230,460	454,621
+	935.00	239983		236,795	691,416
	936.00	246403		243,186	934,602
+	937.00	263753		255,029	1,189,631
+	938.00	271535		267,635	1,457,266
	939.00	279348		275,432	1,732,698
	940.00	287239		283,284	2,015,982
	941.00	295206		291,213	2,307,196
	942.00	303251		299,219	2,606,415
+	943.00	311372		307,303	2,913,718
	944.00	311372		315,463	3,229,180
	344.00	319371		313,403	3,223,100
Step 4 - Outlet Elevations and Storage Volumes					
WQ Orifice Invert Elevation =	938.00				
Elevation of Top of EDv =	938.75				
Secondary Outlet Invert Elevation =	943.50				OKAY
WQ Treatment Volume Provided, Vtreatment =	1,613,159	ft3			
Treatment Vol Provided Relative to EDv, Vtreatment/EDv =	7.89		=	789%	OKAY
Permanent Pool Volume Provided, PPv =	1,457,266	ft3			
Ratio PPv Provided to PPv Required =	5.94		=	594%	OKAY
Step 5 - Outlet (Orifice) Sizing		.		<u> </u>	
	0.75				
Mandanina Hindur He He ad 11.	0.75	ft			
Maximum Hydraulic Head, Hmax =					
Orifice Coefficient, C =	0.6				i
Orifice Coefficient, C = Target (Minimum) Draw-down Time, Td =	24	hr			
Orifice Coefficient, C = Target (Minimum) Draw-down Time, Td = Target Average Discharge, Qavg =	2.37	cfs			
Orifice Coefficient, C = Target (Minimum) Draw-down Time, Td = Target Average Discharge, Qavg = Average Hydraulic Head, Havg =	24 2.37 0.38	cfs ft			
Orifice Coefficient, C = Target (Minimum) Draw-down Time, Td = Target Average Discharge, Qavg = Average Hydraulic Head, Havg = Estimated Orifice Area, Aorifice =	24 2.37 0.38 115.59	cfs	-	0.803	ft2
Orifice Coefficient, C = Target (Minimum) Draw-down Time, Td = Target Average Discharge, Qavg = Average Hydraulic Head, Havg = Estimated Orifice Area, Aorifice = Estimated Orifice Diameter, Dorifice =	24 2.37 0.38	cfs ft	=	1.01	ft
Orifice Coefficient, C = Target (Minimum) Draw-down Time, Td = Target Average Discharge, Qavg = Average Hydraulic Head, Havg = Estimated Orifice Area, Aorifice = Estimated Orifice Diameter, Dorifice = Design Orifice Diameter, Dorifice =	24 2.37 0.38 115.59	cfs ft in2	_		
Orifice Coefficient, C = Target (Minimum) Draw-down Time, Td = Target Average Discharge, Qavg = Average Hydraulic Head, Havg = Estimated Orifice Area, Aorifice = Estimated Orifice Diameter, Dorifice =	24 2.37 0.38 115.59 12.13	cfs ft in2 in	=	1.01	ft

Time to Completely Drain EDv, Td =

Volume Drained in First 8 hr = 61,078


% of EDv = 29.9

%

must be > 24 hr OKAY

must be < 50% OKAY





Existing Conditions

The existing site is a couple of schools with respective parking lots and athletic fields/stadiums. The site consists of woods in good condition, open space, straight row crops and impervious areas. The site's existing watershed is split, with the 46.488 acres draining to the existing detention pond via an on site storm pipe collection system, there is a northern area that bypasses the pond consisting of 28.886 acres and a southern bypass area of 38.485 acres that also drains off site.

Proposed Conditions

The proposed improvements will include constructing a new set of tennis courts, buildings, bleachers, a sidewalk, utilities, and other associated site improvements. Runoff from the site will be collected in a new storm sewer system and routed through an improved Wet Extended Detention Basin, providing both Water Quality Volume and Detention Volume controls to reduce post-construction runoff rates in accordance with the Ohio EPA and City of Piqua Regulations. The detention basin will be located in the western portion of the site at the current pond location as shown on these plans. The detention basin will outlet to a new storm sewer run and ultimately discharge at the 54" culvert opening near the rear of the Upper Valley Career Center. An easement for this storm sewer and connection will be secured with the adjacent property owner.

The downstream 54" culvert was analyzed to assure that there would be no increased impacts due to the improvements and the design accounts for some future expansion.

- Bs - Brookston Silty Clay Loam, 0 to 2 % slopes, Hydrologic Soil Group C/D (17% of site) - CeB - Celina Silt Loam, 2 to 6 % slopes, Hydrologic Soil Group C/D (2.2% of site) - CrA - Crosby Silt Loam, 0 to 2 % slopes, Hydrologic Soil Group C/D (46.7% of site) - CrB - Crosby Silt Loam, 0 to 2 % slopes, Hydrologic Soil Group C/D (2.8% of site) - OdA - Odell Silt Loam, 0 to 2 % slopes, Hydrologic Soil Group C/D (31.3% of site) - C soils used for pre-development analysis; C soils used for post-development analysis.

Know what's below. Call before you dig.

Rainfall Data

Ttannan Bata	_
Storm	24-hr Depth
1-year	2.23
2-year	2.68
5-year	3.29
10-year	3.79
25-year	4.50
50-year	5.08
100-year	5.69

Reference Materials and Methodology for Calculations USDA - Urban Hydrology for Small Watersheds - Technical Release 55 USDA - Web Soil Survey City of Piqua Stormwater Regulations Ohio EPA Permit No 0OHC000006

Runoff Control and Water Quality Requirements

ODNR Rainwater and Land Development Manual

NOAA Altas 14, Volume 2, Version 3

Provide detention as necessary to reduce post-construction runoff rates to pre-development rates in accordance with the Critical Storm Method.

Provide water quality to meet the requirements of Ohio EPA Permit No. OHC000006.

Runoff Control and Water Quality will be achieved with a Wet Extended

Critical Storm Method Calculations

Pre-Development Conditions (Composite) Area = 149.36 acres Composite CN = 83 6.138 acres of Woods in Good Condition (CN=70) 60.301 acres of Open Space Grass in Good Condition (CN=74) 48.877 acres of Straight Row Crops in Good Condition (CN=85) 29.064 acres of Pavement/Building (CN=98) 4.30 acres of Stadium Area (CN=86) 0.68 acres of Cul-de-Sac Pond Area (CN=89)


Post-Development Conditions (Composite)

Tc = 55.6 minutes

Tc = 45.3 minutes

Area = 149.36 acres Composite CN = 87 1.082 acres of Woods in Good Condition (CN=70) 52.479 acres of Open Space in Good Condition (CN=74) 23.113 acres of Straight Row Crops in Good Condition (CN=85) 3.951 acres of Stadium Area (CN=86) 68.005 acres of Pavement/Building (CN=98) 0.68 acres of Cul-de-Sac Pond Area (CN=89) Accounts for some future expansion.

Pre-developed 1 year storm runoff volume = 10.662 ac-ft Post-developed 1 year storm runoff volume = 13.551 ac-ft 27.10% increase in runoff volume Critical Storm = 5 year



SLOPE DESIGN FOR STORM WATER

STORAGE FACILITY POND

ONCE EXCAVATION BEGINS, CONTRACTOR

RIP-RAP (TYPE B) (12" THICK MIN.) -EXTEND RIP-RAP 2' ABOVE THE


POND OUTLET STRUCTURE 607

NOT TO SCALE

NORMAL POOL ELEVATION

100-YR WSE = 943.49

NP = 938.00



OMP



Design: MES Proj: 23.191 Draw: MES Dwg: Check: JDB Tab:

Scale: AS SHOWN 10.18.2024

STORM WATER MANAGEMENT PLAN