



**TENNIS COURT & SITE IMPROVEMENTS 2024
PIQUA HIGH SCHOOL
PIQUA CITY SCHOOL DISTRICT**

ADDENDUM 05

November 26, 2024

Piqua City School District
215 Looney Road
Piqua, OH 45356

This Addendum modifies and shall become a part of the original Contract Documents and is hereby made part of the Bidding Documents for the referenced project.

All bidders shall indicate in their bid/proposal that this Addendum has been received and considered in their bid proposal.

The Addendum items are intended to supplement, clarify or correct parts of the bid proposal package. Items in the addendum shall take precedence over items corrected and shall be of equal value with items supplemented or clarified. Any questions in reference to this addendum must be directed, in writing, to:

Jonathan Schaaf
RDA Group Architects
7662 Paragon Road
Dayton, Ohio 45459
937.610.3440
JRS@rda-group.com

ADDENDUM ITEMS

1. Drawing Sheet C-4.2: MODIFY as follows:
 - 1.1. CHANGE from 4" diameter perforated PVC piping at the perimeter of the tennis courts to 6" diameter perforated PVC piping. [this will now match the Architectural Drawings and Bowser Morner Report]
 - 1.2. CHANGE from 4" diameter perforated PVC piping connections from the Tennis Court underdrains which connect to storm structures 110, 112, and 401 to 8" diameter.
 - 1.3. ADD note: Refer to Architectural Sheet A1.1 for full extent of underdrain design and piping locations within the Tennis Courts.
2. Drawing Sheets A3.1 / A3.2: ADD insulation to the exterior CMU walls at the Storage / Toilet Room Building: Foamed in Place Masonry Wall Insulation, Core-Fill 500 by Tailored Chemical Products or Equal. Fill all open cells and voids in hollow exterior CMU walls.

End.